

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-26445-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 10-33S-13E
1537 feet from S Section Line, 1018 feet from E Section Line
Lease Name: OWNBEY Well #: 1A
County: CHAUTAUQUA Total Vertical Depth: 2119 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 1900 SHAWNEE MISSION PKWY
MISSION WOODS, KS 66205

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 40 | | 10 SX |
| PROD | 4.5 | 2100 | | 240 SX |

Well Type: SWD UIC Docket No: D27322.0 Date/Time to Plug: 07/21/2011 12:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: JUSTIN BARKMAN Company: Phone: (620) 330-7694

Proposed Plugging Method: 100' CEMENT PLUG ON BOTTOM TO COVER PERFORATIONS. 100' CEMENT PLUG AT 800' AND 300' TO SURFACE WITH GEL SPACERS IN BETWEEN.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed 07/21/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" tubing to 2080' gelled hole and spotted 10 sack plug of 60/40 pozmix. Pulled up to 650' and spotted 10 sack plug. Pulled up to 323' and circulated cement to surface. Pulled 2" and topped well off. A total of 75 sacks of cement were used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2058 | 2067 | | |

RECEIVED
NOV 14 2011
KCC WICHITA

RECEIVED

NOV 3 2011 DAS

KCC Chanute Dist. #3

Remarks: PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed

Da a Si

(TECHNICIAN)

cc to MIC 11/15/11
Form CP-2/3
11/16/11