

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-125-02307-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 33-33S-14E
1348 feet from S Section Line, 2167 feet from E Section Line
Lease Name: BERRY Well #: 1P
County: MONTGOMERY Total Vertical Depth: 750 feet)

Operator License No.: 33702

Op Name: MAGNUM ENGINEERING COMPANY

Address: 500 N SHORELINE BLVD STE 322
CORPUS CHRISTI, TX 78471

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/28/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHNIE WATT

Company:

Phone: (918) 914-0124

Proposed Plugging Method: AS DIRECTED BY DISTRICT 3 OFFICE OF KCC. This is an old shot hole well found abandoned in the field and appears to be a pre-1967 vintage. No data is available for this well from KCC. We intend to plug it as per the direction of District 3 office of KCC. Please assign API number as you may deem appropriate. The well number was assigned by us.
Thanks

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 07/28/2011 11:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Couldn't get past bridge at 250'. Tried to wash down outside of 7" and couldn't get 1" to go. Pumped gel down 7" and came back up backside. Pulled 1" and perforated 7" at 250'. Ran 1" to 250' and circulated cement to surface inside and outside 7" casing. Pulled 1" and topped well off. A total of 65 sacks of cement were used to plug this well.

RECEIVED

NOV 1 2011 DAS

KCC Chanute Dist. #3

RECEIVED
NOV 04 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Form CP-2/3

11/7/11