

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01791-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 26-10S-21W  
990 feet from S Section Line, 330 feet from W Section Line  
Lease Name: ZEIGLER Well #: 2  
County: GRAHAM Total Vertical Depth: 3710 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250	0	250 SX
PROD	5.5	3706	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2011 12:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: ROBIN L. AUSTIN Company: RAMA OPERATING CO., INC. Phone: (620) 234-5191

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2011 4:20 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 250' w/250 sxs cement.  
5 1/2" production casing set at 3706' w/100 sxs cement.  
TD 3710'. PBTB 3709'.  
Packer stuck in 5 1/2" casing at 2100'. One joint of tubing and mud anchor below packer.  
Casing has holes.  
Perforated production casing at 1600' - 1200' - 235'.  
Ran tubing to 2050' Shut valves on 5 1/2" and 8 5/8" surface casing - pumped 150 sxs cement with 100# hulls.  
Max. P.S.I. 900#.  
Opened 5 1/2" casing valve and pumped 120 sxs cement mixed with 200# hulls.  
Pulled tubing to 1050' - pumped 65 sxs cement.  
Cement to surface from 5 1/2" casing. Shut 5 1/2" casing valve and pumped 35 sxs cement.  
Cement to surface from surface casing.  
Pulled tubing to surface. Topped casing with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3706	3709		ARBUCKLE

RECEIVED  
NOV 04 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING-TICKET #5222.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

11/7/11

OCT 17 2011