

3080279

4-11

22290

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 5120
 OPERATOR: RANGE OIL CO.
 NAME AND ADDRESS 125 N. MARKET, SUITE 1120
WICHITA, KS 67202

API NUMBER 15- 049-~~21298~~-00-00
 SEC. 3, T 31 S, R 10 E
910 FEET FROM SOUTH SECTION LINE
1130 FEET FROM EAST SECTION LINE
 LEASE NAME DURBIN WELL # 1
 COUNTY ELK
 WELL TOTAL DEPTH 2004 ^{66.13} FEET
 CONDUCTOR PIPE: SIZE _____ FEET _____
 SURFACE CASING: SIZE 8 5/8 FEET 158

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X
 OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR GLAVES DRILLING CO., INC. LICENSE NUMBER 30864
 ADDRESS ROUTE 2, BOX 284, DOUGLAS, KS 67039

COMPANY TO PLUG AT: HOUR: 6:00 PM DAY: 11 MONTH: 4 YEAR: 93

PLUGGING PROPOSAL RECEIVED FROM VERNON GLAVES

(COMPANY NAME) GLAVES DRILLING CO., INC. (PHONE) 316-265-6231

WERE: 50' CEMENT PLUG AT TD, 50' CEMENT PLUG AT 1400', CEMENT 500' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY BILL AUGUSTINE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:00 PM DAY: 11 MONTH: 4 YEAR: 93

ACTUAL PLUGGING REPORT FILLED HOLE WITH 45 VIS. DRILLING MUD, PUMPED 35 SACKS CEMENT THROUGH DRILL PIPE FROM 2004' TO 1925', PUMPED 35 SACKS CEMENT THROUGH DRILL PIPE FROM 1425' TO 1350', PUMPED 240 SACKS CEMENT THROUGH DRILL PIPE FROM 450' TO SURFACE, PUMPED 10 SACKS CEMENT THROUGH DRILL PIPE INTO RATHOLE.

REMARKS: _____
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED James H. Crooner
 (TECHNICIAN)

FORM 2/3 RECEIVED
 STATE CORPORATION COMMISSION

MAY 25 1993

CONSERVATION DIVISION
 Wichita, Kansas

INVOICED

DATE 5-26-93

INV. NO. 3725-7