

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21406-00-00
Spot: NESESE Sec/Twnshp/Rge: 5-32S-21W
962 feet from S Section Line, 330 feet from E Section Line
Lease Name: HARDEN Well #: 2-5 (SE)
County: CLARK Total Vertical Depth: 6610 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5075		WITH 2 SX CMT
SURF	8.625	672		WITH 400 SX CMT
COND	20	51		WITH 5 SX CMT
PROD	5.5	6601	3300	WITH 305 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/25/2011 9:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: SET CIBP @ 5075' WITH 2 SX CMT. PLUG AT 1030' WITH 50 SX CMT. PLUG AT 700' WITH 75 SX CMT. TAG CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2011 11:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG SET CIBP @ 5075' WITH 2 SX CMT. 2ND PLUG PULL CASING TO 1030'. MIX & PUMP 50 SX CMT. 3RD PLUG PULL CASING TO 700'. MIX & PUMP 75 SX CMT W/3% CC. WAIT ON CMT. RAN SANDLINE. TAG TOC @ 700'. PULL REST OF CASING OUT OF HOLE. SDON. 10/26/11; 4TH PLUG TIHWT TO 700'. MIX & PUMP 50 SX CMT W/3% CC. 5TH PLUG PULL TBG TO 250'. MIX & PUMP 40 SX CMT. 6TH PLUG PULL TBG TO 60'. PUMP 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5137	5141		MORROW

RECEIVED
NOV 07 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
NOV - 2 2011
KCC DODGE CITY

Form CP-2/3
11/16/11