

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21363-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 5-32S-21W
2158 feet from S Section Line, 2086 feet from E Section Line
Lease Name: HARDEN Well #: 1-5
County: CLARK Total Vertical Depth: 6536 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5060		WITH 2 SX CMT
CIBP		6100		
SURF	8.625	684		WITH 400 SX CMT
COND	20	82		WITH 10 YDS CMT
PROD	5.5	6532	3000	WITH 375 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/25/2011 9:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: SET CIBP @ 5060' WITH 2 SX CMT. PLUG AT 1020' WITH 50 SX CMT. PLUG AT 720' WITH 75 SX CMT. TAG CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACCLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2011 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG SET CIBP @ 5060' WITH 2 SX CMT. 2ND PLUG PULL CASING TO 1020'. MIX & PUMP 50 SX CMT. 3RD PLUG PULL CASING TO 720'. MIX & PUMP 75 SX CMT W/3% CC. PULL CASING TO 250'. WAIT ON CMT. TAG TOC @ 700'. PULLED REST OF CASING & SDON. 10/26/11: 4TH PLUG TIHWT TO 700'. MIX & PUMP 40 SX CMT W/3% CC. 5TH PLUG PULL TBG TO 250'. MIX & PUMP 50 SX CMT. 6TH PLUG PULL TBG TO 60'. PUMP 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6513	6516		
6168	6172		VIOLA
6154	6156		VIOLA
6148	6152		VIOLA
5116	5122		MORROW

Remarks:

Plugged through:

District: 01

RECEIVED

NOV - 2 2011

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

RECEIVED
NOV 07 2011
KCC WICHITA