

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20837-00-00
Spot: NE Sec/Twnshp/Rge: 4-22S-40W
3924 feet from S Section Line, 1256 feet from E Section Line
Lease Name: SALVATION ARMY Well #: 2
County: HAMILTON Total Vertical Depth: 2800 feet

Operator License No.: 33470
Op Name: PERMIAN REEF, LLC
Address: 2262 WILLOW CIR DR
GREENWOOD, IN 46143

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	377		WITH 225 SX CMT
PROD	5.5	2800	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/19/2011 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARLAND SMITH Company: _____ Phone: (620) 384-4600

Proposed Plugging Method: PUMP 200# HULS & 275 SX CMT DOWN CASING. 75 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2011 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING WITH CMT FROM 2769' TO 0' USING 250# HULLS & 290 SX CMT. PRESSURE TO 500#. FILL ANNULUS WITH 25 SX CMT. PRESSURE TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2765	2775		
2763	2769		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED

OCT 28 2011

KCC DODGE CITY

RECEIVED
NOV 07 2011

KCC WICHITA

11/16/11