

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21390-00-00
Spot: NENENW Sec/Twnshp/Rge: 8-24S-16W
4938 feet from S Section Line, 2953 feet from E Section Line
Lease Name: SMITH A Well #: 2
County: EDWARDS Total Vertical Depth: 4370 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4200 | | WITH 2 SX CMT |
| SURF | 8.625 | 303 | | WITH 275 SX CMT |
| PLG | 4.5 | 4335 | | |
| PROD | 4.5 | 4369 | 2222 | WITH 125 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2011 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4200' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2011 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4200' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1116' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 589' WITH 50 SX CMT. 3RD PLUG AT 341' WITH 40 SX CMT. 4TH PLUG AT 62' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|---------------|
| 4259 | 4281 | | Mississippian |

RECEIVED
NOV 07 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

NOV - 4 2011

KCC DODGE CITY

Form CR-2011

11/16/11