

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23675-00-00
Spot: S2SWNENW Sec/Twnshp/Rge: 3-21S-12W
1132 feet from N Section Line, 1645 feet from W Section Line
Lease Name: W S Well #: 1-3
County: STAFFORD Total Vertical Depth: 3555 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	344		WITH 375 SX CMT
PROD	5.5	3547	2600	WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2011 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3380' & 5 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 370' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2011 12:01 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3350' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 668' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 374' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3461	3464		
3448	3451		
3444	3448		
3438	3442		
3430	3434		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
NOV 07 2011
KCC WICHITA

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT 28 2011
KCC DODGE CITY

Form CP-20

VA/15/11