

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22100-00-00
Spot: W2SENESE Sec/Twnshp/Rge: 13-22S-12W
1692 feet from S Section Line, 445 feet from E Section Line
Lease Name: WILLINGER Well #: 2
County: STAFFORD Total Vertical Depth: 3642 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	341		WITH 275 SX CMT
PROD	5.5	3637	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3490' & 5 SX CMT. 5 1/2" CASING SQUEEZED @ 760-761' WITH 250 SX CMT. RUN TBG TO 660' INSIDE OF 5 1/2". CIRCULATE 5 1/2" CASING TO SURFACE WITH CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2011 10:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

5 1/2" CASING SQUEEZED AT 760-761' WITH 250 SX CMT. SANDED BOTTOM TO 3350' WITH 5 SX CMT ON TOP WITH DUMP BAILER. RAN TBG TO 665' & CIRCULATED CMT TO SURFACE UP 5 1/2" CASING WITH 100 SX CMT. PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2" WITH 5 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 600 PSIG WITH 2 1/2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3612	3618		
3544	3550		
760	761		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

RECEIVED
OCT 28 2011
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
NOV 07 2011
KCC WICHITA

FORM CC-243

11/15/11