

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-20062-00-00  
Spot: E2NW Sec/Twnshp/Rge: 12-14S-27W  
1320 feet from N Section Line, 3300 feet from E Section Line  
Lease Name: SUTCLIFFE Well #: AC 2  
County: GOVE Total Vertical Depth: 4340 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	270	0	150 SX
DVT		1999		
PROD	5.5	4339	0	180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2011 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING COMPANY, I Phone: (620) 793-2315

Proposed Plugging Method: Ordered 485 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Plug through tubing.  
Operator requested all cement plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2011 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 270' w/150 sxs cement.  
5 1/2" production casing set at 4339' w/180 sxs cement.  
DV Tool set at 1999' and cemented with 340 sxs.  
TD 4340'. Original PBTD at 4278'. CIBP at 3890'.  
Ran tubing to 3804' - pumped 100 sxs cement mixed with 300# hulls.  
Pulled tubing to 2800' - pumped 100 sxs cement mixed with 100# hulls.  
Pulled tubing to 1800' - pumped 100 sxs cement mixed with 100# hulls.  
Pulled tubing to 900' - pumped 100 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 5 1/2" production casing and pumped 80 sxs cement.  
Connected to 8 5/8" surface casing. Casing immediately pressured to 300#.

Perfs:

Top	Bot	Thru	Comments
3916	3920		Below CIBP
3852	3854		Above CIBP
3846	3848		Above CIBP

RECEIVED  
NOV 08 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #43,522.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

NOV 02 2011

Form CP-2/3  
11/16/11