

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20392-00-00
Spot: N2SESENE Sec/Twnshp/Rge: 9-11S-40W
3070 feet from S Section Line, 330 feet from E Section Line
Lease Name: BELLAMY Well #: 1-9
County: WALLACE Total Vertical Depth: 5190 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 7851 S ELATI ST STE 201
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/06/2011 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: JAY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 11/06/2011 11:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3000' w/25 sxs.
2nd. Plug at 2200' w/100 sxs.
3rd. Plug at 300' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: ALLIED.CEMENTING COMPANY.

Plugged through: DP

RECEIVED
NOV 09 2011
KCC WICHITA

District: 04

Signed Case Morris
(TECHNICIAN)

NOV 07 2011

Form CP-2/3

✓ 11/15/11