

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23204-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 35-10S-20W  
4240 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ARMBRISTER Well #: 1  
County: ROOKS Total Vertical Depth: 3853 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	135 SX
PROD	5.5	3849	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2011 1:30 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.  
Port collar at 1625'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2011 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3397' - pumped 11 sxs gel - followed with 75 sxs cement with 200# hulls.  
Pulled tubing to 1630' - pumped 200 sxs cement with 200# hulls - cement circulated.  
POOH. Hooked up to casing and pumped 25 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Hooked up to Braden head and pumped 15 sxs cement.  
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3793	3795		
3777	3779		
3767	3770		
3762	3764		
3754	3757		
3634	3641		KC

RECEIVED  
NOV 09 2011  
KCC WICHITA

Remarks: QUALITY CEMENTING-TICKET #168.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN) CM

11/15/11

NOV 07 2011