

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22760-00-00  
Spot: SENENE Sec/Twnshp/Rge: 34-10S-20W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: TOWNS Well #: 2  
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261	0	200 SX
PROD	5.5	3799	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2011 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.  
DV Tool set at 1633'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2011 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3397' - pumped 11 sxs gel - followed with 75 sxs cement with 200# hulls.  
Pulled tubing to 1630' - pumped 150 sxs cement with 100# hulls - cement circulated.  
POOH. Hooked to casing and pumped 25 sxs cement.  
Max. P.S.I. 250#. Shut in.  
Hooked up to Braden head and pumped 5 sxs cement.  
Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
3789			ARBUCKLE
3417			LKC

Remarks: QUALITY CEMENTING-TICKET #167.  
Plugged through: TBG

RECEIVED  
NOV 09 2011  
KCC WICHITA

District: 04

Signed Ray A Dinkel  
(TECHNICIAN)

CM

✓ 11/15/11

NOV 07 2011