

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22269-00-00
Spot: W2NESWNE Sec/Twnshp/Rge: 31-13S-21W
1650 feet from N Section Line, 1940 feet from E Section Line
Lease Name: BONGARTZ Well #: 1-31
County: TREGO Total Vertical Depth: 4205 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	150 SX
T1	2.375	4100		
PC		1737		
PROD	5.5	4204	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.
Port collar at 1737' w/150 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2011 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped down the top 50 sxs cement with 100# hulls - followed with 12 sxs gel - followed with 240 sxs cement with 100# hulls. - full Tied onto backside - pumped 7 sxs cement. S.I.P. 500#.

Perfs:


Top	Bot	Thru	Comments
4120	4124		
4090	4096		
3872	3879		
3766	3770		
3695	3698		
3595			

Remarks: ALLIED CEMENTING COMPANY-TICKET #38361.

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)

CM

RECEIVED
NOV 09 2011
KCC WICHITA

Form CP-2/3

11/15/11

NOV 07 2011