

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20166-00-00
Spot: NENWNE Sec/Twnshp/Rge: 35-20S-35W
445 feet from N Section Line, 1941 feet from E Section Line
Lease Name: LIVINGSTON Well #: 2-35
County: WICHITA Total Vertical Depth: 5090 feet

Operator License No.: 34319
Op Name: SODOCO, LLC
Address: PO BOX 369
LITTLETON, CO 80160

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	266		WITH 170 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/25/2011 12:30 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: GARY DOKE Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 10/25/2011 2:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED
NOV 10 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
NOV - 4 2011
KCC DODGE CITY

Signed Steve Durrant
(TECHNICIAN)