

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5123
Name: Pickrell Drilling Company, Inc.
Address 1: 100 S. Main
Address 2: Suite 505
City: Wichita State: KS Zip: 67202 + 3738
Contact Person: Jack Gurley
Phone: (316) 262-8427
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LKC "H" Depth to Top: 3915 Bottom: 3922 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 063-20062 • 00 • 00
Spot Description: _____
C E/2 NW Sec. 12 Twp. 14 S. R. 27 East West
1,320 Feet from North / South Line of Section
660-3300 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Gove
Lease Name: Sutcliffe A-C Well #: 2
Date Well Completed: 04-14-1971
The plugging proposal was approved on: 10-31-11 (Date)
by: Darrell Dipman (KCC District Agent's Name)
Plugging Commenced: 10-31-11
Plugging Completed: 10-31-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC "H"	Oil	Surface	8 5/8	270	None
		Production	5 1/2	4331	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Through 2 3/8" tubing open-ended spotted 100 sx Cement w/ 300# of hulls @ 3804, spotted 100 sx. cement w/ 100# of hulls @ 2809', spotted 100 sx cement w/ 100# of hulls @ 1816', circ. cement to surface w/ 100 sx spotted @ 800'. After pulling tubing out used 80 sx cement to top off and fill back to surface. Tied into 8 5/8 x 5 1/2 annulus, pressured to 400#, held OK. All cement 60/40 Poz 4% gel.

Plugging Contractor License #: 99996 Name: Allied Cementing Co., LLC
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Pickrell Drilling Company, Inc.
State of Kansas County, Sedgwick ss. _____
Jack Gurley Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Jack Gurley

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 09 2011
KCC.WICHITA