

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior Inc.
Address 1: P.O. Box 399
Address 2: _____
City: Garden City State: Ks. Zip: 67846 + _____
Contact Person: Jody Smith
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other; _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 057-20749 • 00 • 00
Spot Description: _____
SE SW NW NW Sec. 24 Twp. 27 S. R. 22 East West
1,044 Feet from North / South Line of Section
354 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ford
Lease Name: Herman Well #: 1-24
Date Well Completed: 10/12/11
The plugging proposal was approved on: NA (Date)
by: Eric Maclaren (KCC District Agent's Name)
Plugging Commenced: 10/14/11
Plugging Completed: 10/14/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	85/8	430'	0

RECEIVED
NOV 10 2011
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Drill pipe was run to 1450', 50sx cement plug was pump, Pulled pipe to 690', 80sx cement plug was pumped. Pulled pipe to 460', 50sx plug was pumped. Pulled pipe to 60', 20sx cement plug was pumped. Pumped 30sx cement in rat hole and 20sx in mouse hole. All cement was 60/40 poz, 4% gel and 1/4# Floseal.

Plugging Contractor License #: 5929 Name: Duke Drilling Co.Inc.
Address 1: 410 center point at main Address 2: 100 S. Main st.
City: Wichita State: Kansas Zip: 67202 + 3737
Phone: (316) 267-1331

Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.

Jody Smith Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

AK