

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5259 Name: MAI OIL OPERATIONS, INC Address 1: 8411 PRESTON RD, STE 800 City: DALLAS State: TX Zip: 75225 + 5520 Contact Person: ALLEN BANGERT Phone: (214) 219-8883 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 15-053-21268-00-00 Spot Description: SE NW SE NW Sec. 10 Twp. 16 S. R. 10 East West 1,670 Feet from North / South Line of Section 1,700 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: ELLSWORTH Lease Name: KOZISEK Well #: 1 Date Well Completed: 11/07/2011 The plugging proposal was approved on: 11/07/2011 (Date) by: VIRGIL CLOTHIER (KCC District Agent's Name) Plugging Commenced: 11/07/2011 Plugging Completed: 11/07/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: SURFACE, 8 5/8, 420, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 185 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal, 1st plug @ 3404' with 35 sacks, 2nd plug @ 1300' with 35 sacks, 3rd plug @ 1000' with 35 sacks, 4th plug @ 470' with 35 sacks, 5th plug @ 60' to surface with 25 sacks, 20 sacks for rat hole, by Quality (Ticket #516), job completed @ 6:00 pm on 11/7/2011.

RECEIVED NOV 14 2011 KCC WICHITA

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING, INC Address 1: 8 NORTH MAIN Address 2: PO BOX 276 City: ELLINWOOD State: KANSAS Zip: 67526 + Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: MAI OIL OPERATIONS, INC State of KANSAS County, BARTON, ss.

JILL WAHLMEIER (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier



Southwind Drilling, Inc.
Plugging Orders & Reports

Lease: Kozisek #1

Plugging Received from KCC Representative:

Name: Virgil Clothier Date: 11-7-11 Time: 2:30 P:m

1 st plug @ <u>3404</u> feet, <u>35</u> sacks	Stands <u>55</u>
2 nd plug @ <u>1300</u> feet, <u>35</u> sacks	Stands <u>21</u>
3 rd plug @ <u>1000</u> feet, <u>35</u> sacks	Stands <u>16</u>
4 th plug @ <u>470</u> feet, <u>35</u> sacks	Stands <u>7 1/2</u>
5 th plug @ <u>60</u> feet, <u>25</u> sacks	Stands <u>RECEIVED</u>

Mousehole: _____ sacks

Rathole: 20 sacks

Total Cement Used: 185 sacks

Type of cement: 6 1/4 Poz 4% Cel 1/4" F10

Plug Down @ 6:00 P:m 11-7-11

Call KCC When Completed:

Name: Virgil Clothier Date: 11-10-11 Time: 11:00

NOV 14 2011
KCC WICHITA