

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32504
Name: Blackhawk Production Company
Address 1: 1607 Oakmont
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Aaron Werth
Phone: (785) 625-2041

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-26,143-00-00
Spot Description: 40'S & 20'E of
SW, SW Sec. 14 Twp. 13 S. R. 20 East West
620 Feet from North / South Line of Section
680 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Calvert Well #: 4
Date Well Completed: Calvert
The plugging proposal was approved on: 5/19/2011 (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 10:30AM 5/20/2011
Plugging Completed: 2:00PM 5/20/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Pipe	8 5/8	1505	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(1st Plug @ 3818'W/25sks)(2nd Plug @ 1522'W/25sks)(3rd Plug @ 732'W/100sks)(4th Plug @ 40'W/10sks)(30sks In Rat Hole)(15sks In Mouse Hole)(Total 205sks 60/40Poz 4%Gel W/1/4#CF/sk-By Quality Oilwell Cementing-Completed @ 2:00PM 5/20/2011)(Circulated 1st Plug 15 Minutes W/56Vis MUD)(Displaced Plugs W/MUD)

RECEIVED

NOV 18 2011

KCC WICHITA

Plugging Contractor License #: 31548 Name: Discovery Drilling Co., Inc.
Address 1: P.O. Box 763 Address 2: 1029 Reservation Road
City: Hays State: Kansas Zip: 67601 + 0763
Phone: (785) 623-2920

Name of Party Responsible for Plugging Fees: Blackhawk Production Company
State of Kansas County: Ellis ss.
Aaron J. Werth Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct. so help me God.

Signature: Aaron J. Werth