

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline

County. Sec. 5 Twp. 16 Rge. 1W (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE SW SE

Lease Owner F.S. Williams

Lease Name Karber Well No. 2

Office Address Box 746, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. Sept 23rd, 1950 19

Application for plugging filed. October 1950 19

Application for plugging approved. October 1950 19

Plugging commenced. October 20th, 1950 19

Plugging completed. October 27th, 1950 19

Reason for abandonment of well or producing formation

No Oil

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee

Producing formation. Depth to top. Bottom. Total Depth of Well 2701' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	125	8 5/8"	125'	0
		10)	2674	5"	2674'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 6 sacks of cement at bottom of hole. Shot pipe off at 2400'
Pulled pipe and mudded hole to 130' Set Rock bridge and put 20 sacks
of cement at 130' Finished mudding hole and put 5 sacks cement at top of surface

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1950 11-21-50

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to F.S. Williams
Address Box 746 McPherson, Kansas.

STATE OF _____, COUNTY OF _____, ss.

_____ (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *F. S. Williams*
agent

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of November, 1950
Lillian H. Thurman
Notary Public.

My commission expires 6-22-1952

PLUGGING
FILE SEC 5 T 16 R 1W
BOOK PAGE 34 LINE 4

COMPANY: E. S. Williams
 CONTRACTOR: Mallard Drilling Company
 BARN: Karber #2
 LOCATION: NE SW SE Sec. 5-18-1W
 Saline County, Kansas
 COMMENCED: 9-9-50 rotary
 9-18-50 cardwell
 COMPLETED: 9-16-50 rotary
 9-21-50 cardwell

0	to	125	Surface sand
125		225	Shale and shells
225		405	Anhydrite - shale
405		580	Lime and shale
580		760	Sandy lime and shale
760		1070	Lime and shale
1070		1430	Shale and shells
1430		1905	Shale and lime
1905		2075	Shale and lime
2075		2180	Shale and lime
2180		2285	Lime
2285		2370	Shale and lime
2370		2575	Lime and shale
2575		2670	Shale and lime
2670		2672	Lime--cherty
		2672	C.D. Rotary
2672		2702	Chat--water
		2702	C.D. Cardwell

Set 126' of 8 5/8" surface pipe. Cemented with 90 sacks cement.

Set 5 1/2" pipe at 2672. Cemented with 40 sacks cement.

TOPS: Chat 2669

Measurements taken from derrick floor.

DRY, ABANDONED AND PLUGGED

RECEIVED
 CORPORATION COMMISSION
 SEP 20 1950
 DIVISION
 KANSAS

CERTIFICATE

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Karber #2, NE SW SE, Sec. 5-18-1W, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

PLUGGING
 FILE SEC 5 T 18 R 1W
 BOOK PAGE 34 LINE 4

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 26th day of September 1950.

Harold Wright

My commission expires 11/4/52