


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

COMANCHE County, Sec. 24 Twp. 31S Rge. (E) 20 (W)

Location as "NE/CNWxSWx" or footage from lines. C SW NE
Lease Owner MAGAW & ZIMMER
Lease Name ELLIS Well No. 1
Office Address 22 PARK AVE. BLDG., SUITE 220, OKLAHOMA CITY, OKLA.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed Nov. 18, 19 65
Application for plugging filed (PHONE 11/18/65) Nov. 29, 19 65
Application for plugging approved Nov. 18, 19 65
Plugging commenced Nov. 18, 19 65
Plugging completed Nov. 18, 19 65
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	100	13-3/8"	100'	NONE
		0	640	8-5/8"	640'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 300 FEET. SET FIRST PLUG WITH 1/2 SACK HULLS, 2 SACKS DRY CEMENT, PLUG, THEN 23 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG WITH 1/2 SACK HULLS AND 10 SACKS CEMENT. PLUG RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1965

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 29TH day of NOVEMBER, 1965

My commission expires FEBRUARY 1, 1968.
[Signature] BARBARA J. LAYTON Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ELLIS #1
C SW NE SECTION 24-31S-20W
COMANCHE COUNTY, KANSAS

COMMENCED: NOVEMBER 8, 1965
COMPLETED: NOVEMBER 19, 1965

OPERATOR - MAGAW & ZIMMER INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	85	SAND	
85	100	SHALE	RAN 5 JOINTS OF 13-3/8" CASING, SET @ 100' w/100 SACKS CEMENT.
100	155	RED BED	
155	357	RED BED AND SHALE	
357	640	SHALE AND SHELLS	RAN 27 JOINTS OF 8-5/8" CASING, SET @ 640' w/250 SACKS CEMENT.
640	1610	RED BED AND SHALE	
1610	1925	SHALE	
1925	2680	SHALE AND LIME	
2680	2790	LIME	
2790	3010	LIME AND SHALE	
3010	3095	SHALE AND CHALK	
3095	3994	SHALE AND LIME	
3994	4060	SHALE AND SAND	
4060	4100	LIME, SHALE AND SAND	
4100	4310	LIME AND SHALE	
4310	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW NE SECTION 24-31S-20W, COMANCHE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RECEIVED
COMANCHE COUNTY, KANSAS

NOV 30 1965

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS CONSERVATION DIVISION
COUNTY OF SEDGWICK)
) Wichita, Kansas

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 23RD DAY OF NOVEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.