

15-033-20037-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1974  
8-16-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name B.D. & M.P. Gilbert

Complete Address 600 E 42nd St New York, NY - 10017

Lease Name Dale Well No. 1-13

Location C NW/SW Sec. 13 Twp. 33 Rge. 18 (E) (W) W

County Comanche Total Depth 5177

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation

Address Box 187 Medicine Lodge, KS License No. \_\_\_\_\_

Operation Completed: Hour 11:00 AM Day 15 Month 8 Year 1974

The above well was plugged as follows:

520 ft 8 5/8 surface cemented with 350 sacks. 5176 ft 5 1/2 long string

cemented with 100 sacks. Top perf. 5157 ft. Sand to 5130 ft, 5

sacks cement with bailer. Pulled 3950 ft 5 1/2. Set 10 ft rock bridge

at 240 ft. Fill hole with 4 yds redimix to surface.

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/16/74

INV. NO. 9713-W