

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-033 20, 4/3-00.00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Ste. 300, Wichita, Kansas 67202

Lease Name Gregg-Booth "A" Well No. 3

Location C SE SE NW Sec. 8 Twp. 33 Rge. 16W (East) (West)

County Comanche Total Depth 5100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Clarke Oilfield Services

Address 107 W. Fowler, Medicine Lodge, KS License No. 583

Operation Completed: Hour: 2:30PM Day: 31 Month: 8 Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

60' of 10 3/4" cond. W/300 sks

989' of 8 5/8" W/225 sks

4 1/2" csg. set @ 5099' W/225 sks BB to 4990'

Perfs 4888' to 4892' SB to 4860' & 4 sks

Pump 15 gel 8 hulls 10 gel, release plug and displace W/150 sks

50/50 pozmix 4% gel 3% C.C. Cemented by Allied

Recovered 4051' of 4 1/2" csg. SIP 100#

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-25-81

INV. NO. 74576W

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP - 25 1981
Wichita, Kansas
CONSERVATION DIVISION