

*40*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1963  
1-14-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Continental Oil Co.

Complete Address: P. O. Box 494, Medicine Lodge, Kansas

Lease Name *SHIMER*  
Shriver Well No. B 1

Location C - NE - NE Sec. 18 Twp. 33S Rge. 16 (E) (W) W

County Comanche Total Depth 5060

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Strata Drilling Co. Inc.

Address: 10th and O'Fall, Great Bend, Kansas License No.     

Operation Completed: Hour 3:30AM Day 9th Month Jan. Year 1963

The Above well was plugged as follows:

390' of 10 1/2" surface pipe. 994' of 8 5/8" surface pipe which was cut  
off and 303' of pipe was recovered from hole. Hole was filled with heavy  
mud to 270', 1/2 sack hulls and 1st cementing plug and 25 sacks cement,  
filled hole with mud to 40', 2nd cementing plug with 1/2 sack hulls ahead  
of plug, 25 sacks of cement to base of cellar. Rat hole bridged and  
cemented with 2 sacks

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/14/63  
INV. NO. 6422-w

Signed: Archie Elving  
Well Plugging Supervisor