

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 033-20293-0000 (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Hackney Well No. 1

Location SE NE Sec. 18 Twp. 33S Rge. 18 (E) (W) X

County Comanche Total Depth 5375

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling Service.

Address 620 S. Lincoln. Liberal, Ks. 67901 License No. 511

Operation Completed: Hour 12 N. Day 15 Month 9 Year 1979

The above well was plugged as follows:

498' 8 5/8" casing (KB) w/500 sax cement. 4 1/2" casing set 5362' w/
325 sax cement. Plug back to 5331'-CIB plug set at 5000'-Preforated
at 5258' to 65 & 4878' to 80-Pumped 25 sax common cement to 4430'-
Pull 3815' 4 1/2" casing. Pumped 40 sax common cement plug at 480'-
through casing. Build bridge at 35' & 12 sax cement to 5' below GL.
Cemented by Sargent.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1979
9-19-79

INVOICED

I hereby certify that the above well was plugged as herein stated

DATE 9-19-79

INV NO. 0490-W

Conservation Division
Wichita, Kansas
Signed: [Signature]
Well Plugging Supervisor