

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-033-20659-00-00

LEASE NAME Schweitzer #3

WELL NUMBER C SE NE

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 33S RGE. 20W (E) or (W)

COUNTY Comanche

Date Well Completed 9/16/84

Plugging Commenced 5/2/85

Plugging Completed 6/11/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

ADDRESS 2915 Classen Blvd. Okla City, Ok. 73106

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	597'	none
				4 1/2"	4869'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pipe was collapsed @ 275'. No pipe recovery. Pumped bottom with 100# hulls & 50 sacks cement to 4050'. Shot pipe at 4000', 3500', & 270'. Pumped down casing till cement circulated around backside with 100 sks. Pumped 50 sacks cement down 8 5/8. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.



R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of June, 19 85

My Commission Expires:



JUN 17 1985

CONSERVATION DIVISION
 Wichita, Kansas



GUARD
SIDEWALL NEUTRON
LOG

COMP. HALLIBURTON OIL PRODUC. WELL #3 SCHWEITZER FIELD COLLIER FLATS COUNTY COMANCHE ST. KS.	COMPANY HALLIBURTON OIL PRODUCING COMPANY		
	WELL #3 SCHWEITZER		
	FIELD COLLIER FLATS		
	COUNTY COMANCHE		STATE KS.
	API NO. LOCATION C-SE-NE		OTHER SERVICES FLAP
SEC. 26	TWP. 33S	RGE. 20W	
PERMANENT DATUM	GROUND LEVEL	ELEV. 1853	ELEV.: K.B. 1860
LOG MEASURED FROM	KELLY BUSHING 7	FT. ABOVE PERM. DATUM	D.F.
DRILLING MEASURED FROM	KELLY BUSHING		G.L. 1853
DATE	08/26/84	08/26/84	08/26/84
RUN NO.	GAMMA	LONG GUARD	NEUTRON
DEPTH-DRILLER	4870	4870	4870
DEPTH-WELEX	4870	4870	4870
BTM. LOG INTER.	4842	4856	4869
TOP LOG INTER.	SURFACE	CASING	STATE CORPORATION COMMISSION
CASING-DRILLER	8 5/8 e 597	e	e
CASING-WELEX			
BIT SIZE	7 7/8		
TYPE FLUID IN HOLE	PREMIX/CHEMICAL		
DENS. ; VISC.	9.4 ; 47		
PH ; FLUID LOSS	11.0 ; 12.8 ML		
SOURCE OF SAMPLE	MUD PIT		
RM e MEAS. TEMP.	.36 e 75 F	e F	e F
RMF e MEAS. TEMP.	.31 e 75 F	e F	e F
RMC e MEAS. TEMP.	.49 e 75 F	e F	e F
SOURCE RMF RMC	CALC. ; CALC.		
RM e BHT	.22 e 127 F	e F	e F
TIME SINCE CIRC.	3 HOURS		
TIME ON BOTTOM	6:30 8-26-84		
MAX. REC. TEMP.	127 Fe TD	Fe	Fe
EQUIP. ; LOCATION	1891 ; PRATT		
RECORDED BY	G. FOX		
WITNESSED BY	MR. BILL SLADEK		

RECEIVED
MAR 13 1985
STATE CORPORATION COMMISSION
Wichita, Kansas