

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

RWD
04-19-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Comanche SEC. 28 TWP. 33 RGE. 20 X/W
Location as in quarters or footage from lines:
SW NE

	2	8	

Locate Well
correctly on above
Section Platt.

Lease Owner Samuel Gary Oil Producer
Lease Name Foster Well No. #28-7
Office Address #4 Inverness Court East Englewood, Colorado 80112
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 12/1/81 - producer; 6/12/82 - dry hole
Application for plugging filed Yes
Plugging commenced 6/12/82
Plugging completed 6/12/82
Reason for abandonment of well or producing formation Well proven to be commercially non-productive
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie
Producing formation N/A Depth to top _____ bottom _____ T.D. 5336'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>KRM Petroleum had originally drilled & plugged the well as the #1-28 Foster. Therefore, KRM set surface casing as follows:</u>			<u>765'</u>	<u>8-5/8"</u>		<u>No</u>
<u>SGOP subsequently re-entered the location as a washdown and ran 4 1/2" production casing as follows:</u>			<u>5327.70'</u>	<u>4 1/2"</u>		<u>Yes (3683')</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well plugged and abandoned as follows:

Bottom plug set at 4900'-5284' with 25 sx cmt and 1 sx hulls
Pulled to & plug 1100'-1160' with 20 sx
Pulled to & plug 810'- 710' with 50 sx
Surface plug 40'- 0' with 10 sx

Sargent's Casing Pulling Service pulled 90 joints overall (3683', including starting joint of 12'). Job completed at 4:30 p.m. 6/12/82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
620 South Lincoln Liberal, Kansas 67901

STATE OF Colorado COUNTY OF Denver, ss.

B. D. Crismon (employee of owner) or ~~XXXXXXXXXXXXXXXXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. D. Crismon
#4 Inverness Court East
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 82

Tracey S. Norton
Notary Public.

My Commission expires: My Commission Expires March 30, 1986