

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-033-26062-00-00

API NUMBER Spud 4-6-70

LEASE NAME Schweitzer

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 33s RGE. 20W (E) or (W)

COUNTY Comanche

Date Well Completed

Plugging Commenced 4-1-97

Plugging Completed 4-14-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

525 Central Park Dr.

ADDRESS Central Park 1 #210 Oklahoma City, OK 73105

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1016'	none
				4 1/2	4293'	3509'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Sanded bottom to 4745' & ran 4 sks cement. Shot at 3509', worked pipe free. Pulled pipe to
1060', loaded hole w/10 sks gel & 50 sks cement. Gel circulated. Pulled casing and found holes
from 320' to 360'. Pulled all casing. Pumped 125 sks cement down 8 5/8. Shut in 650 psi.
Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Halliburton Oil Producing Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
 statements, and matters herein contained and the log of the above-described well as filed t
 the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 97

Jane Derberg
 Notary Public

My Commission Expires:

