

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20072-DD-DD

LEASE NAME Norton #1

WELL NUMBER C NE SE

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 33s RGE. 20w(E) or (W)

COUNTY Comanche

Date Well Completed

Plugging Commenced 5/6/85

Plugging Completed 5/13/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

ADDRESS 2915 Classen Blvd. Okla City, Ok. 73106

PHONE#(405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	363'	none
				8 5/8	1100'	none
				4 1/2"	5188'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pipe was collapsed. No pipe recovery. Pumped bottom with 200# hulls, & 50 sacks cement to 4400'. Shot pipe at 2000'. Pumped 100 sacks cement down 4 1/2" and 200 sacks down 8 5/8. (60/40 poz 6% gel 3% c.c.)
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of June, 19 85

My Commission Expires:



JUN 17 1985

RECEIVED
STATE CORPORATION COMMISSION
Notary Public
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84



15-D33-26072-60-20

Gamma Ray Neutron Laterolog

FILE NO.	COMPANY	MIDWEST OIL CORPORATION		
	WELL	NORTON NO. 1		
	FIELD	COLLIER FLATS	<i>TOPS</i>	
	COUNTY	COMANCHE	STATE	KANSAS
	LOCATION:	C NE-SE		Other Services
	SEC 26	TWP 33S	RGE 20W	A/L-CAL

Permanent Datum	GROUND LEVEL	Elev.	1831	KB	1838
Log Measured from	KELLY BUSHING	7 Ft. Above Permanent Datum		DF	1836
Drilling Measured from	KELLY BUSHING			GL	1831

Date	8-14-70				
Run No.	ONE				
Depth—Driller	5300				
Depth—Logger	5298				
Bottom Logged Interval	5297				
Top Logged Interval	SURF				
Casing—Driller	8 5/8@1100	@	REL @	@	
Casing—Logger					
Bit Size	7 7/8"				
Type Fluid in Hole	SALT MUD		MAR 18 1985		
Density and Viscosity	9.7	49			
pH and Fluid Loss	6.4	5.2 cc			
Source of Sample	FLOW LINE				
Rm @ Meas. Temp.	.28 @ 90 °F	.09 @ 134 °F	@ °F	@ °F	
Rmf @ Meas. Temp.	@ °F	.06 @ 134 °F	@ °F	@ °F	
Rmc @ Meas. Temp.	@ °F	.28 @ 134 °F	@ °F	@ °F	
Source of Rmf and Rmc		CHART	CHART		
Rm @ BHT	.09 @ 134 °F	@ °F	@ °F	@ °F	
Time Since Circ.	2 HRS.				
Max. Rec. Temp. Deg. F.	134 °F	°F	°F	°F	
Equip. No. and Location	LL-1004	GB			
Recorded By	MILLS				
Witnessed By	MR. JOHNSON				

FOLD HERE ↓