

15-033-10016-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Comanche County, Sec. 20 Twp. 33S Rge. (E) 18(W)

Location as "NE/CNW%SW%" or footage from lines SW NE

Lease Owner Eason Oil Company

Lease Name Deewall Well No. 1

Office Address Box 18755 Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed 1-3 1966

Application for plugging approved 1-5-66 19

Plugging commenced 1-20-66 19

Plugging completed 1-31-66 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 5350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 13 3/8 | | -0- |
| | | | | 8 5/8 | 2600 | 2013 |
| | | | | 5 1/2 | 5350 | 3235 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 25 sack cement plug to 4900 feet. Filled hole with mud. Shot casing at 4616'. Shot at 4487, 4003, 3747, 3320, 3225 feet. Pulled 102 joints of 5 1/2" casing. Shot 8 5/8" casing at 2308' and at 2157 and 2012'. Pulled 60 joints of 8 5/8" casing. Built rock bridge from 240 to 230 feet. Put 50 sacks cement from 230 to 180 feet. Loaded hole with mud to 40 feet. Built rock bridge from 40 to 30 feet and capped with 30 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1966

2-14-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gayle E. Toland

Address Box 94336, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

(employee of owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]

VICE PRESIDENT

Box 18755, Oklahoma City, Okla
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of February, 1966

My commission expires SEPTEMBER 11, 1966

Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
 STATE CORPORATION COMMISSION

FEB 14 1966

2-14-66

CONSERVATION DIVISION
 WICHITA, KANSAS

WELL #1
 C SW NE SECTION 20-33S-18W
 COMANCHE COUNTY, KANSAS

COMMENCED: NOVEMBER 21, 1965
 COMPLETED: DECEMBER 11, 1965

OPERATOR - EASON OIL COMPANY

| DEPTH | | FORMATION | REMARKS |
|-------|------|-------------------|---|
| FROM | TO | | |
| 0 | 95 | CLAY | |
| 95 | 130 | SAND | |
| 130 | 272 | RED BED | RAN 13-3/8" CASING TO 269', SET w/300 SACKS CEMENT. |
| 272 | 920 | RED BED | |
| 920 | 1395 | RED BED AND SHALE | |
| 1395 | 1650 | SHALE AND SHELLS | |
| 1650 | 1840 | SHALE | |
| 1840 | 2170 | SHALE AND SHELLS | |
| 2170 | 2255 | SHALE AND LIME | |
| 2255 | 2600 | LIME | RAN 80 JOINTS OF 8-5/8" CASING, SET @ 2599' w/125 SACKS CEMENT. |
| 2600 | 2985 | LIME | |
| 2985 | 3680 | LIME AND SHALE | |
| 3680 | 3715 | LIME | |
| 3715 | 3940 | LIME AND SHALE | |
| 3940 | 4060 | SHALE | |
| 4060 | 4450 | SHALE AND LIME | |
| 4450 | 4500 | SAND | |
| 4500 | 4880 | LIME | |
| 4880 | 5130 | LIME AND SHALE | |
| 5130 | 5350 | LIME | |
| 5350 | TO | | RAN 170 JOINTS OF 5 1/2" CASING, SET @ 5349' w/125 SACKS CEMENT. |

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL
 DRILLED IN THE C SW NE SECTION 20-33S-18W, COMANCHE COUNTY, KANSAS, TO THE BEST OF MY
 KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND
 STATE, ON THIS 16TH DAY OF DECEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSON-
 ALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT
 AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED
 FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND
 YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.