

To: 1020671 5-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,743-0000
C SE SW ., SEC. 12 , T 31 S, R 30 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9534

Lease Name Borth Well # 24-12

Operator: Giant Exploration & Production Co.
Name & Address P.O. Box 2810
Farmington, NM 87401-2810

County Meade 181.67
Well Total Depth 5590 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1644

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 4 Year: 19 93

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 5885', Perfs at 4672-80, 4840-48, 4920-32', All squeezed off, PBTD 5518'
Perfs at 5454-64, 5504-12'

1st plug pump 2 sx hulls and 25 sx cement at perfs, displace with mud with tubing,

2nd plug pump 25 sx cement at 3370' with tubing,

3rd plug shoot pipe off, pull to 1700' and pump 50 sx cement,

4th plug pump 40 sx cement at 700', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5 p.m. Day: 6 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, displaced with mud with tubing,

2nd plug pumped 25 sx cement at 3370' with tubing,

3rd plug shot pipe off at 2547', pulled to 1700' and pumped 50 sx cement,

4th plug pumped 40 sx cement at 700',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2547' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 5-17-93

WELL NO. 37725

Signed Glenn R. Barlow (TECHNICIAN)