

1 060508

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,817-0000

NE NW SW, SEC. 3, T 31 S, R 21 W/EX

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9657

Lease Name Strodtman Well # 1-3

Operator: Quintana Petroleum Corp.

County Clark 171.28

Name & Address 818 17th Street, Suite 610

Well Total Depth 5270 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 730 ✓

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 pm Day: 12 Month: March Year: 19 85

Plugging proposal received from Billy Faulds

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5274' PBTD 5231.07', Perfs at 5243-47'

1st plug sand back to 5190' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:10 pm Day: 12 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5190' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 15 1985 3-15-85

Maximum pressure 400 psi and shut in 0

Remarks: Recovered 4500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% ca. Wichita, Kbya Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-18-85

INV. NO. 7370

3-12

Signed Paul A. Luthi (TECHNICIAN) SD