

1052017

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS. 67202

APT NUMBER 15- 025-20,487-0000
C NW SW, SEC. 4, T 31 S, R 21 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3399
Operator: Farrar Pump & Supply Co. Inc.
Name & Address: P.O. Box 209,
Medicine Lodge, KS 67104

Lease Name Imel Well # 1-4
County Clark
Well Total Depth 5252 170.69 feet
Conductor Pipe Size feet
Surface Casing: Size 8 5/8 feet 625

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 27 Month: 2 Year: 19 96

Plugging proposal received from Richard McIntyre
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

logs: 4 1/2" at 5243' w/200 sx cement. Open hole 5243-52'
1st plug at 1200' with 50 sx cement,
2nd plug at 650' with 50 sx cement,
3rd plug at 40' with 10 sx cement.

RECEIVED
KANSAS CORP COM
1996 FEB 29 AM 11:30
2-29-96

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 p.m. Day: 27 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st attempt to plug on 1/23/96 failed because of hole in surface pipe.
Pumped plugs through tubing:

1st plug at 1200' with 10 sx gel and 50 sx cement,
2nd plug at 650' with 50 sx cement,
3rd plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3532' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, you may observe this plugging.)

Signed Richard W. Lacy (TECHNICIAN)

DATE MAR 05 1996

INV. NO. 44942 APR 26 1996