

1 090649

1-23

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
136 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 025-20,793 -0000
NE NE SE, SEC. 5, T 31 S, R 21 W/E
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399
Operator: Farrar Pump & Supply Co. Inc.
Name & Address: P.O. Box 209,
Medicine Lodge, KS 67104

Lease Name Imel Well # 2-5
County Clark 171.11
Well Total Depth 5265 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 643

Abandoned Oil Well Gas Well Input Well SYD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 23 Month: 1 Year: 19 96

Plugging proposal received from John

(company name) Farrar Pump & Supply Co. Inc. (phone) 316-886-3763

Work: 4 1/2" at 5251' w/200 sx cement, Open hole
1st plug sand back to 5200' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
Wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:40 a.m. Day: 23 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 5200' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 100 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3553' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
and observe this plugging.

DATE 1-30-96

INV. NO. 44749

Signed [Signature] (TECHNICIAN)

RECEIVED
KANSAS CORP COM
1996 JAN 26

1-2 APR 26 1996