

To: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

API NUMBER 15-025-20,101-06-61

SE, Sec. 6, T 31 S, R 21 W/E

2086 feet from N/S section line

2086 feet from W/E section line  
 SWD 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name Dailey Well # 3-6

Operator: Mesa Petroleum Co.  
 Name & Box 2009  
 Address Amarillo, TX 79105

County Clark

Well Total Depth 5250 feet 170.62

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 604

Abandoned Oil Well        Gas Well        Input Well        SWD Well X D&A       

Other well as hereinafter indicated       

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:30 am Day: 27 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Don Horton

(company name) Sargents Casing Pulling (phone) 316-624-7455  
5144 to 46

were: 4 1/2 set at 5250'. PBTD 5200. Perfs 5172 to 80. CIBP at 5160 --

Pumped 2 sx hulls, 35 sx cement through 4 1/2 to bottom. 2nd plug 1200' pumped

50 sx through 4 1/2 spotted 50 sx through 4 1/2 at 650'. 3rd plug pulled pipe

from hole, built solid bridge at 40' and filled to surface with 10 sx cement.

Hole was full of mud before plugs were spotted.

Signed Steve Clumont  
 (TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 10:00 am Day: 30 Month: January Year: 19 84

ACTUAL PLUGGING REPORT Hole was full of mud before shooting off pipe and spotting

plugs. 1st plug pumped 2 sx hulls, 35 sx cement through 4 1/2 to bottom. 2nd plug

at 1200' pumped 50 sx through 4 1/2 spotted 50 sx through 4 1/2 at 650'. 3rd plug

pulled pipe from hole, built solid bridge at 40' and filled to surface with 10

sx cement. They recovered 3020 4 1/2"

Remarks: Used sack common cement by Sargents Casing Pulling.

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 02 1984  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
 and that I (~~XXX~~ / did not) observe this plugging.

Signed Steve Clumont  
 (TECHNICIAN)

FORM CP-2/3  
 Rev. 9-82

INVOICED

DATE 2-6-84

INV. NO. 0072

1-30