

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-025-29,762-0000

SWNE, Sec. 13, T. 31 S., R. 21 W/4

1980 feet from N/E section line

1980 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 57171

Lease Name Bouryman "C" Well # 1

Operator: TXO Production Corp  
Name & Address 200 W Douglas, Suite 300  
Wichita, Kansas  
67202

County Clark?

Well Total Depth 5300 feet 172.25

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8" feet 683

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Freeman Drilling Co. License Number 5106

Address 251 N. Water, Wichita, Kans 67202

Company to plug at: Hour: 11:00 PM, Day: 12 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Bill Cheshire

(company name) Freeman Drilling Co. (phone) \_\_\_\_\_

were: 1st plug @ 1120' w 50 lb cement.

2nd plug @ 720' w 50 lb cement.

3rd plug on solid bridge @ 40' to 0' w 10 lb cement.

Circulate 15 lb cement in rat holes 10 lb cement in mouse hole.

Sum cementing accomplished the plugging w/ 60/40 ppg

w/ 29 gell & 3% CC.

Signed Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 3:00 AM, Day: 13, Month: 1, Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 1120' w 50 lb cement. spotted through drill pipe w/ hole full of heavy mud. 2nd plug @ 720' w 50 lb cement. spotted through drill pipe w/ hole full of heavy mud. 3rd plug filled hole to 40' w heavy mud built solid bridge w/ bulls & rubber plug and spotted 10 lb cement through drill pipe filling hole from 40' to 0'. Circulated 15 lb cement through drill pipe in rat hole. Circulated 10 lb cement through drill pipe in mouse hole.

Remarks: \_\_\_\_\_

Sum Cementing out of Medicine Lodge accomplished the plugging w/ 60/40 ppg w/ 29 gell & 3% CC.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~was~~ / did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 1-20-84

INV. NO. 9216-1N

FORM CP-2/3  
Rev. 9-82