

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Kingman

County. Sec. 4 Twp 28 Rge 5 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C 1/2 N SE SE

Lease Owner Laura Jane Oil Co., Inc.

Lease Name Seward Well No. 2

Office Address 817 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 12-10 19-51

Application for plugging filed 12-10 19-51

Application for plugging approved 12-10 19-51

Plugging commenced 11:30 AM 12-10 19-51

Plugging completed 12:30 PM 12-10 19-51

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Dwight Lillie

Producing formation Depth to top Bottom Total Depth of Well 3868 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Soil		0	15			
Sand		15	130			
Shale		130	153	8 5/8	153'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 150'. Set wood plug with 1/2 sack hulls 15 sacks cement. Filled hole to 10' of bottom of cellar, set wood plug 1/2 sack hulls. Filled hole to bottom of cellar with 8 sacks cement. The 15 sacks of cement on bottom plug was mixed and run through drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Laura Jane Oil Co., Inc.

Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Jacobs  
Box 556 Great Bend Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of December, 19-51

Coral F. Lair  
Notary Public.

My commission expires 6/28/52

28-8390-s 6-51-20M

PLUGGING  
FILE SEC 4 T 28 R 5  
BOOK PAGE 120 LINE 13

RECEIVED  
DEC 15 1951  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLING LOG

WELL NAME: Seward # 2  
 OWNERS: Laura Jane Oil Col, Inc.  
 CONTRACTORS: Laura Jane Oil Col, Inc.  
 COMM: 11-28-51  
 COMP: 12-10-51

LOCATION: <sup>CN<sub>2</sub></sup> SE SE SE, 4-28-5W  
 Kingman County, Kansas  
 ELEVATION: 1427 RB  
 CASING RECORD: 153" @ 8 5/8"  
 PRODUCTION: Dry

<u>FORMATION</u>	<u>TO</u>		<u>TOPS</u>
Soil - Sand	130		
Shale	153		
Shale - Shells	440		
Anhydrite	505		
Shale - Shells	845		
Shale - Lime	1870		
Sand - Sandy Shale	1925	K. C. Lansing	2969
Shale - Shells	2025	Mississippi Chert	3784
Lime - Shale	2970		
Lime	3425		
Shale - Lime	3784		
Chat	3868	TD Rotary	

I certify that the above is a true and correct copy of the log of the Seward # 2, SE SE SE, 4-28-5W, Kingman County, Kansas to the best of my knowledge.

LAURA JANE OIL COMPANY, INC.

BY: James Armour  
 JAMES ARMOUR

Sworn and subscribed to before me this 15th day of December, 1951

Carol F. Fair  
 NOTARY PUBLIC

My Comm. expires 6-28-52

**PLUGGING**  
 FILE SEC 4-28-5W  
 BOOK PAGE 13

RECEIVED  
 STATE DEPT. OF REVENUE  
 DIVISION  
 DEC 17 1951