


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County. Sec. 1 Twp. 28S Rge. 5 (E) (W) X

Location as "NE/CNW*SW*" or footage from lines SW SE SW

Lease Owner Leben Drilling, Inc.

Lease Name Simmons Well No. 1

Office Address P. O. Box 486 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 11-10-65 19__

Application for plugging approved 11-13-65 19__

Plugging commenced 11-21-65 19__

Plugging completed 12-18-65 19__

Reason for abandonment of well or producing formation _____

Dry

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3803 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	212	None
				2 1/2	3803	None
				5 1/2	None	732

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in.

Killing gas. Mixed and pumped 10 sacks of cement.

Shot pipe at 3100' - 2950'.

Shot pipe at 2800' - 2500'. Gas blowing in. Killing gas.

Pumped 5 sacks of cement into 5 1/2" casing at 1600'.

Cleaned out cellar. Working pipe. Shot pipe at 1000' - 900' - 800' and 700'.

Pulling pipe. Fighting gas. Build mud rock bridge at 200'. Dumped 25 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of December, 1965

Alvin O. [Signature]

Notary Public.

My commission expires May 27, 1969

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY:	Martin & Keller
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	SIMONS #1
LOCATION:	SW SE NW Sec. 1-28S-5W KINGMAN COUNTY, KANSAS
COMMENCED:	1-24-64
COMPLETED:	2-4-64

0	65	Surface Clay & Sand
65	410	Redbed & Shale
410	770	Shale
770	795	Anhydrite
795	995	Shale with Lime Streaks
995	1425	Lime & Shale
1425	1730	Shale & Shells
1730	2025	Lime & Shale
2025	2440	Shale & Lime
2440	3095	Lime & Shale
3095	3225	Lime
3225	3262	Lime & Shale
3262	3365	Lime
3365	3475	Lime & Shale
3475	3580	Lime
3580	3770	Lime & Shale
3770	3830	Lime
	<u>3830</u>	<u>Rotary Total Depth - Set 5 1/2"</u> Casing

Set 8 5/8" used surface casing @ 212' with landing joint cemented with 175 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Simons #1 well, located SW SE NW Section 1, Township 28 South, Range 5 West, Kingman County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS }
COUNTY OF BARTON } SS

Subscribed and sworn to before me, a Notary Public, in and For Barton County, Kansas, this 11th day of February, 1964.

Ulanda Nichols

Ulanda Nichols, Notary Public

My Commission Expires:
April 1, 1967