




STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 6 Twp. 28 Rge. 4W (~~E~~) (~~B~~) (~~W~~)  
Location as "NE/CNWSW" or footage from lines C W/2 NW NW  
Lease Owner The Shallow Water Refining Company  
Lease Name Bartholomew Unit, Tract 18 Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-18-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9-22-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3814 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	None
				5-1/2"	3759'	3300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3814', sanded hole to 3750' and dumped 5 sacks of cement @ 3750' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 225' to 215' and dumped 20 sacks of cement @ 215'. Mudded hole to 30' and capped well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul J. August  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1965

My commission expires May 20, 1968  
Milton J. Volin Notary Public.

15-773-01614-0000

XERO COPY

XERO COPY

XERO COPY

XERO COPY

KANSAS WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS


Sheet 18 R

COMPANY WESTGATE GREENLAND OIL CO.  
FARM Davis "B" NO. 1

SEC. 6 T. 28 R. 4W  
LOC. CW/2 NW NW

TOTAL DEPTH 3782  
COMM. 12-1-50 COMP. 12-27-50  
SHOT OR TREATED  
CONTRACTOR Jackson Drilling Corp.  
ISSUED 4-14-51

COUNTY Sedgwick  
KANSAS



CASING

8 5/8" 195' cem. w/135 sx  
5 1/2" 3759' cem. w/75 sx

ELEVATION 1419

PRODUCTION Pot. 22 BO &  
60% wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	9
clay & shale	70
shale & shells	625
salt & shale	780
lime & shale	1060
shale	1160
lime & shale	1220
lime	1330
lime & shale	2500
shale	2535
lime	3400
lime & shale	3693
shale	3715
lime	3740
lime (mississippian)	3760
lime cored, reamed core	
hole	3766
lime	3782
Total Depth	
Tops:	
Mississippi	3722

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1965

CONSERVATION DIVISION  
Wichita, Kansas

Cored from 3760 - 3766. Full recovery.  
DST: 3759 - 3782, open 1 hr. rec. 330' oil & gas cut foamy mud.  
1000 gallons Dowell Service  
All measurements from top of derrick floor.