

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-20,284-000

LEASE NAME Wiechman #1

WELL NUMBER _____

SPOT LOCATION NE/4 SE/4

SEC. 32 TWP. 28 SRGE. 3W (E) or (W)

COUNTY Sedgwick

Date Well Completed _____

Plugging Commenced 12/5/84

Plugging Completed 12/11/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Raymond Oil Co., Inc.

ADDRESS One Main Place, Suite 900, Wichita, Ks. 67202

PHONE # (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4228'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	256'	none
				5 1/2"	4220'	3284'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged horizon with sand to 4180' & 5 sacks cement. Shot pipe at 3284' & pulled 80 joints of pipe. Plugged well with 3 hulls, 6 gel, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. RECEIVED
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Wichita, Kansas

(Address) Box 347, Chase, Ks. 67524

CONSERVATION DIVISION
Wichita, Kansas

DEC 17 1984

SUBSCRIBED AND SWORN TO before me this 14 day of December, 1984


IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

[Signature]
Notary Public

My Commission expires: _____

2 050203

API NUMBER 15-173-20,284-6000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-NE/SW, SEC. 32, T 28 S, R 3 W

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Wiechman Well # 1

Operator: Raymond Oil Co. Inc.
Name & Address: 1. main place suite 900
Wichita, Ks. 67202

County Sedgwick

Well Total Depth 4328 ¹⁴⁰⁻⁶⁶ feet

Conductor Pipe: Size ✓ feet ✓

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 176 Chase, Ks.

Company to plug at: Hour: 8:00 A. Day: 6 Month: Dec Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) _____

were: 5 1/2" casing was set @ 4320 & part @ 4217-22
sand back to 4180 & dump 5sx. of cement with a
dump bailer. shot & pull pipe. Pumped 100sx. cement
in the top.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1984

Plugging Proposal Received by Glen L Ward
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:00 AM Day: 11 Month: Dec Year: 19 84

ACTUAL PLUGGING REPORT sanded back to 4180 & Dumped 5sx.
of cement on sand. shot & pulled 3304 ft. of 5 1/2"
Casing in good cond. Pumped thru 8 5/8" swage 6sx.
gel 3sx. Hulls & 100sx. 60/40 posmix. max. PSI 200
close in @ 100 PSI.

Remarks: united ticket # 7120

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 12/8/84
INV. NO. 6800

Signed Glen L Ward
(TECHNICIAN)