


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-173-20360-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sedgwick County, Sec. 32 Twp. 28 Rge. 3 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NW SE
Lease Owner Sunburst Exploration Co.
Lease Name Jacobs Well No. #1
Office Address Suite 708 One Main Place Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Dry Hole.
Date Well completed 5-27 1981
Application for plugging filed 5-27 1981
Application for plugging approved 5-27 1981
Plugging commenced 5-27 1981
Plugging completed 5-27 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4325'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	256'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 265', 1/2 sk. hulls, plug, 35 sx. cement.
Mud to 40', 1/2 sk. hulls, plug, 12 sx. cement.
5 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas Suite 500 Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 1981

Carolyn J. Tjaden
Carolyn J. Tjaden-----Notary Public.

My commission expires



RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

15-173-20360-0000

OPERATOR: Sunburst Exploration Co. Suite 708 One Main Place Wichita, Ks.
 CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Jacobs Well No. #1

Sec. 32 T. 28 R. 3W Spot C NW SE

County Sedgwick State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 256' with _____ Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 4325'

Drilling Commenced: 5-15-81 Drilling Completed 5-27-81

Formation	From	To	Tops
Cellar	0	7	Kansas City 3129
Shale, Salt	7	970	Simpson 4204
Lime, Shale	970	1625	
Shale, Lime	1625	2160	
Shale	2160	2212	
Lime	2212	2340	
Shale, Lime	2340	2560	
Lime, Shale	2560	2730	
Shale	2730	2855	
Sand	2855	2870	
Sand, Shale	2870	2949	
Sand, Shale, Lime	2949	3025	
Shale, Lime	3025	3129	
Lime	3129	3296	
Shale, Lime	3296	3370	
Lime	3370	3606	
Shale, Lime	3606	3897	
Lime	3897	4103	
Shale	4103	4204	
Sand	4204	4325	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION
Wichita, Kansas