

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER N/A 15-095-00728-00-01
LEASE NAME Walter (Rohlman)
WELL NUMBER 1
990 ft. from S Section Line
2970 ft. from E Section Line
SEC. 28 TWP. 29 RGE. 7 (E) or (W)
COUNTY Kingman

LEASE OPERATOR R & B Oil & As, Inc.
ADDRESS 111 N. Blaine, Attica, KS 67009
PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191

Character of well oil **RECEIVED**

(Oil, Gas) D&A, SWD, input, Water Supply Well
The plugging proposal was approved on 4/17/03 **MAY 14 2003** (date)

by Doug Louis **KCC WICHITA** (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Mississippi Depth to Top 4180 Bottom 4288 T.D. 4290

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS							CASING RECORD						
Formation	Content	From	To	Size	Put in	Pulled out							
				8 5/8	250	none							
Miss	Oil & Gas			5 1/2	4288	2631							

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Sand at 4130, bail 5 sacks cement. Shot pipe at 3212, 2842, 2631,, came loose. Pull 42 joints to 1200', pump 35 sacks cement. Pull to 700, pump 35 sacks cement. Pull to 300, circulate with 90 sacks cement. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.
STATE OF Kansas COUNTY OF Harper, ss.
Randy Newberry

(Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Randy Newberry
(Address) 111 N. Blaine, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 12th day of May, 20 03

Jane Swingle, Notary Public
My commission Expires: 1-6-07

Form CP-4
Revised 05-88

