


15-095-01212-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Kingman County, Sec. 28 Twp. 29 Rge. 7 (E) W. (W)  
Location as "NE/CNWxSWx" or footage from lines 1650' W. and 330' N. of E/4 Cor.  
Lease Owner Cities Service Oil Company  
Lease Name Handkins Well No. 3  
Office Address Box 144, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 24 19 60  
Application for plugging filed August 24 19 60  
Application for plugging approved August 24 19 60  
Plugging commenced August 24 19 60  
Plugging completed August 25 19 60  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation None Depth to top - Bottom - Total Depth of Well 4260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	408'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

4260-300' mud.  
300-295' wood plug and hulls.  
295-246' 15 sacks cement.  
246- 35' mud.  
35' to base of cellar, wood plug, hulls and 10 sacks cement.  
2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
09-21-1960  
SEP 21 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Lohmann-Johnson Drilling Company, Inc.  
Address Evansville, Indiana

STATE OF Kansas COUNTY OF Barton, ss.  
John D. Forsyth (employee of owner) or township operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John D. Forsyth  
Box 144, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of August, 19 60

My commission expires March 12, 1963. W. B. Smith Notary Public.

15-095-01212-0000  
**WELL RECORD**

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 3 FARM Handkins

LOCATION 330' North and 1650' West of E/4 Corner

Section 28, Township 29, Range 7W

ELEV. 1524 D.F. (1522 Gr.) CO. Kingman STATE Kansas

IP. Dry hole. P. and A. August 25, 1960

PERFS. ....

FRAC. .... ACID None

T.D. 4260' P.B.T.D. .... GRAV/GOR. ....

DRLG. COMM. August 8, 1960 COMP. August 24, 1960 CONTRACTOR Lohmann & Johnson Drlg. Co., Inc.

**CASING RECORD:**

8-5/8" at 408' with 275 sacks cement.

**FORMATION RECORD:**

red rock	0-410
shale and lime	1133
lime	2035
lime and shale	2180
shale	2410
lime and shale	2515
shale and lime	2820
lime and shale	2945
shale and lime	3001
lime	3105
lime, sand and shale	3234
shale and lime	3325
lime	4260 T.D.

Slope Tests (Sperry Sun):

400'	- 1/2°
1000'	- 1°
1400'	- 0°
2000'	- 1°
2500'	- 1°
3000'	- 3/4°
3500'	- 1/2°
4000'	- 1 1/2°

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 SEP 21 1960  
 CONSERVATION DIVISION  
 Wichita, Kansas