

15-095-01213-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Kingman County, Sec. 28 Twp. 29 Rge. 7 (E) W. (W)  
 Location as "NE/CNW/SW" or footage from lines 330' S. & 330' W. of NE Cor.  
 Lease Owner Cities Service Oil Company  
 Lease Name Handkins Well No. 2  
 Office Address Box 144, Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed February 22 19 59  
 Application for plugging filed February 23 19 59  
 Application for plugging approved February 23 19 59  
 Plugging commenced February 23 19 59  
 Plugging completed February 23 19 59  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
 Producing formation - Depth to top - Bottom - Total Depth of Well 4267 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	418'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4267-240', heavy mud.  
240-186', wood plug, 1/4 sack hulls and 18 sacks cement.  
186'-40', heavy mud.  
40' to base of cellar, wood plug, 1/4 sack hulls and 10 sacks cement.

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 19 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Barbour Drilling Company  
 Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover  
Box 144, Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 59  
W. D. Smith Notary Public.  
 My commission expires March 12, 1959.

PLUGGING  
 FILE SEC. 28 T. 29 R. 7W  
 BOOK PAGE 20 LINE 36

WELL RECORD

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Company WELL # 2 FARM Handkins

LOCATION 330' South and 330' West of NE Cor.

Sec. 23, Twp. 29, Rge. 7E.

ELEV. 1530 (1528 Gr.) CO. Kingman STATE Kansas

IP. Dry hole. P. & A. 2-23-59

PERFS. ....

FRAC. .... ACID None

T.D. 4267' PBTD. .... GRAV/GOR. ....

DRLG. COMM. February 7, 1959 COMP. February 23, 1959 CONTRACTOR Harbour Drlg. Co.

CASING RECORD:

6-5/8" at 418' with 275 sacks cement.

FORMATION RECORD:

clay and red bed	0-220
red bed and shale	1175
shale and shells	1405
lime and shale	1675
lime	1735
lime and shale	1950
shale	2900
shale and lime	2715
lime and shale	2940
lime	3060
lime and shale	3310
lime	3792
lime and shale	3855
lime	3930
lime and shale	3990
lime	4213
lime and chert	4267 T.D.

Hoebner	3087
Douglas	3125
Lansing	3321
Base Kansas City	3821
Mississippi	4100
Pen.	167'
T.D.	4267

D.S.T. 4102-25, open 1 hour, gas in 43 minutes, recovered 46' mud; I.B.H.P. 1500' in 30 minutes, I.F. 0%, P.F. 0%, F.B.H.P. 1450' in 30 minutes.

D.S.T. 4125-55, open 1 hour, recovered 56' mud; I.B.H.P. 1450' in 30 minutes, I.F. 0%, P.F. 0%, F.B.H.P. 1230' in 30 minutes.

Slope Tests (Totco):

118'	-	8°
390'	-	0°
500'	-	8°
1000'	-	3/4°
1355'	-	11°
1380'	-	14°
1757'	-	3/4°
2340'	-	8°
2931'	-	1-3/4°
3300'	-	8°
3638'	-	1°
4009'	-	1°

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1959  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 28 T. 29 R. 7W  
BOOK PAGE 20 LINE 36