

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 29 Twp. 29S Rge. 7W (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW  
Lease Owner Pickrell Drilling Company  
Lease Name Oak "A" Well No. #1  
Office Address 705 Fourth National Bank Building, Wichita, 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed 5-8-60 19 60  
Application for plugging filed " 19  
Application for plugging approved " 19  
Plugging commenced " 19  
Plugging completed " 19  
Reason for abandonment of well or producing formation Dry and Abandoned



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4222 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 240'. Bridge hole and cemented with 20 sacks.  
Heavy mud to 40', bridge hole and cemented with 9 sacks of cement to bottom of cellar. Plugged rat hole with 1 sack of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebits*  
705 Fourth National Bank Building  
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of May, 19 60

My commission expires August 13, 1961  
Ruth M. Sullivan Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita 2, Kansas  
LOCATION: Oak "A" #1  
SE SE NW, Sec. 29-29S-7W  
Kingman County, Kansas  
CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

Rotary Drilling Commenced 4-7-60  
Rotary Drilling Completed 5-8-60

CASING RECORD: 245' (12 jts.) 8-5/8" OD Casing. Set at 250', cemented with 100  
100 sacks. Cement circulated. Completed 6:45 A.M., 4-7-60.

Dry and Abandoned.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

190'	Red Bed and Shells		
245'	Red Rock		Circ. for samples:
825	Shale	3812	
935	Shale and Shells	4135	
1075	Lime and Shale	4145	
1280	Lime, Shale, Salt	4172	
1350	Lime	4222	
1500	Lime and Shale		Slope Tests;
3377	Shale, Sand, Lime		
3475	Lime & Shale	2000	0°
3525	Lime	3000	0°
3840	Lime & Shale	4000	0°
3985	Lime		
4019	Lime & Shale		S.L.M.
4122	Lime		
4145	Mississippi	2000	OK
4222	Rotary Total Depth	3000	OK
		4000	OK

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1960  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. Sebitts, Partner

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 12th day of May, 1960, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1961

[Signature]  
Notary Public  
Ruth M. Sullivan