


15-095-00280-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Kingman County, Sec. 36 Twp. 29 Rge. 8W (E) (W)  
Location as "NE/CNW/SW" or footage from lines. SW SW SW

Lease Owner Rupp-Ferguson Oil Co. / Sierra Petroleum Co-Contr.

Lease Name ALBRIGHT Well No. 1

Office Address 523 Petroleum Bldg, Wicht, Ks / 420 W. Douglas Ave, Wichi

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 3/1/57 19

Application for plugging filed 2/28/57 19

Application for plugging approved 2/28/57 19

Plugging commenced 3/1/57 19

Plugging completed 3/1/57 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4270' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	205	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 4270' up to 200'. Set wood plug at 200' with 1/3 sack hulls and 20 sacks cement up to 160'. Filled hole with heavy mud from 160' up to 30'. Set wood plug with 1/3 sack hulls and 10 sacks cement to cellar 0. Job complete 3:00 p.m. 3/1/57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc  
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 57  
My commission expires 1-30-61.  
MARGIE COOPER Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
03-06-1957  
MAR 6 - 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 36 T 29 R 8W  
BOOK PAGE 145 LINE 5

RUPP-FERGUSON - Owner

Sierra Petroleum Co., Inc. - Contr.

ALBRIGHT #1

SW SW SW Sec. 36-29S-8W  
Kingman County, Kansas

Total Depth: 4270'

Elev: 1569 KB

Comm: 2/14/57

Comp: 3/1/57

Casing:

Cement:

8 5/8" casing @ 205'

with 135 sacks cement

FORMATION

DEPTH

Red Bed - Shale	205
Shale & shells	1225
Lime & shale	2930
Lime	2993
Lime & shale	3045
Lime	3158
Lime & shale	3453
Lime	4006
Lime & shale	4180
Lime	4189
Lime	4213
Miss	4242
Lime & shale	4270

Tops:	Kansas City	3422
	Mississippi	4170

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker  
C. T. Honaker

Subscribed and sworn to before me this 4th day of March, 1957.

Margie Cooper  
Notary Public

My commission expires: 1-30-61.

PLUGGING  
FILE SEC 36 T 29 R 8W  
BOOK PAGE 145 LINE 5

RECEIVED  
STATE CORPORATION COMMISSION  
03-06-1957  
MAR 6 - 1957  
CONSERVATION DIVISION  
Wichita, Kansas