

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 36 Twp. 29S Rge. 8W (W)

Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Aylward Drilling Co.
Lease Name Albright Well No. 1
Office Address 909 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-17-67 19
Application for plugging filed 12-17-67 19
Application for plugging approved 12-17-67 19
Plugging commenced 12-17-67 19
Plugging completed 12-17-67 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4245' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 225', plug, 25 sks. cement
Mud to 40', 1/2 sk. hulls, plug, 10 sks. cement
2 sks. cement in rathole

STATE CORPORATION COMMISSION
12-20-1967
DEC 20 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1967

My commission expires April 1, 1971
Ulana Nichols Notary Public.

DRILLER'S LOG

COMPANY: Aylward Drilling Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: ALBRIGHT #1
 LOCATION: C SE NW SECTION 36-29S-8W
 KINGMAN COUNTY, KANSAS
 COMMENCED: 12-9-67
 COMPLETED: 12-17-67.

0	233	Red Rock
233	1210	Shale, Shells
1210	1222	Anhydrite
1222	1600	Shale, Shells
1600	2410	Lime, Shale
2410	2660	Shale, Lime
2660	3160	Lime, Shale
3160	3245	Shale, Lime
3245	3285	Sand
3285	3370	Shale, Lime
3370	3413	Sand
3413	4180	Lime
4180	4230	Chat
4230	4245	Chert, Lime
	<u>4245</u>	<u>RTD - D. & A.</u>

RECEIVED
 CONSERVATION DIVISION

DEC 20 1967

CONSERVATION DIVISION
 WICHITA, Kansas

8 5/8" 28# used surface casing set @ 233' cemented with 185 sacks
 Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Albright #1 Well, located
 C SE NW of Section 36, Township 29 South, Range 8 West, Kingman
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 19th day of December, 1967.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1971