

1060471

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,456-0000
C NE SW, SEC. 17, T 31 S, R. 21

1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Daily Well # 4-17

Operator: Imperial Oil Company

County Clark 173.29

Name & Address 720 4th Financial Center

Well Total Depth 5332 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 631

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 23 Month: January Year: 1985

Plugging proposal received from Bill Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5332' PBD 5281 Perfs at 5220-26'

1st plug sand back to 5120' and dump 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:50 pm Day: 23 Month: January Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 5120' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1985

Maximum pressure 400 psi and shut in 300 psi

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered 3537' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(If applicable) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED

DATE 2-6-85

INV. NO. 6848