

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-025-20.271-0003

700, Sec. 32, T 31 S, R 21 W/K

700 feet from N/K section line

600 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name McPhail Well # 1-32

Operator: Mesa Petroleum Co  
Name & Address Box 18950  
Oklahoma City, OK  
73154

County Clark

Well Total Depth 5340 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 607

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike Procter Casing Pullers License Number \_\_\_\_\_

Address Suite 417, 3022 N.W. Expressway, Oklahoma City, OK 73112

Company to plug at: Hour: \_\_\_\_\_ Day: 15 Month: DEC. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Charles Behrens

(company name) Procter (phone) \_\_\_\_\_

were: Pump 25 sy @ 5100'. Shoot off 4 1/2 and  
spot 25 sy at free point. Then by spotting cement  
through 4 1/2 as it comes out of the hole, locate  
a plug @ 1020' w/ 70 sy cement and @ 750' w/ 40 sy  
cement and a top plug 40'-0' w/ 10 sy cement using  
50/50 Pozmix, 4% gel-3% CC.

Signed R. Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:00 PM Day: 15 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.  
Cemented by Danell.

Remarks: 4 1/2 @ 5327 - Perf 5164-70  
rec. 2100' of 4 1/2"

I hereby certify that the above plugging instructions were given as herein stated  
and that I ~~did~~ <sup>STATE CORPORATION COMMISSION</sup> did not observe this plugging.

INVOICED  
DATE 12-28-82  
INV. NO. 2051-4

RECEIVED  
DEC 20 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Signed R. Barluttan  
(TECHNICIAN)

\$173.55